

# UNITED SIKHS ORG.

## HAIYAN RELIEF CROSSING LA-IS

| <b>FOR ONE HOUSE BUDGET</b> |                         |                             |          |        |              |              |              |                     |
|-----------------------------|-------------------------|-----------------------------|----------|--------|--------------|--------------|--------------|---------------------|
| S.NO                        | NAME OF ITEM            | SIZE                        | QUANTITY | PRIZE  | SUB TOTAL    | TOTAL        | \$           | IN US\$             |
| 1                           | WOOD                    | 2*5*10                      | 4        | 233    | 932          |              | 44.05        | 21.16               |
| 2                           |                         | 2*5*16                      | 5        | 373    | 1865         |              | 44.05        | 42.34               |
| 3                           |                         | 2*5*8                       | 6        | 186    | 1116         |              | 44.05        | 25.33               |
| 4                           |                         | 2*2*20                      | 15       | 181    | 2715         |              | 44.05        | 61.63               |
| 5                           | G.I.S. SHEETS           | 3*6*.4                      | 18       | 213    | 3834         |              | 44.05        | 87.04               |
| 6                           | IREAN ROAD FOR BEAM     |                             | 54       | 118    | 6372         |              | 44.05        | 144.65              |
| 7                           | CEMENT                  |                             | 17       | 222    | 3774         |              | 44.05        | 85.68               |
| 8                           | HALLO BLOCKS            | 4*8*12                      | 250      | 12     | 3000         |              | 44.05        | 68.10               |
| 9                           | RIDGE ROLL              |                             | 15       | 180    | 2700         |              | 44.05        | 61.29               |
| 10                          | PLYWOOD FOR BEAMS       |                             | 6        | 650    | 3900         |              | 44.05        | 88.54               |
| 11                          | SAND/GRAVEL             | Estimated + -               |          |        | 1500         |              | 44.05        | 34.05               |
| 12                          | NAILS                   | Estimated + -               |          |        | 400          |              | 44.05        | 9.08                |
| 13                          | LABOUR                  | 1. CARP ENTER &<br>2 LABOUR |          | 3 DAYS | 2000         |              | 44.05        | 45.40               |
| 14                          | BAMBOO/NIPAHUT /PLYWOOD |                             | 12       | 650    | 7800         |              | 44.05        | 177.07              |
| 15                          | MISCELLANEOUS           |                             |          |        | 2500         |              | 44.05        | 56.75               |
| <b>TOTAL IN PESOS</b>       |                         |                             |          |        | <b>44408</b> | <b>44408</b> | <b>44.05</b> | <b>1008.13 US\$</b> |

**NOTE:-** 1. This house is studio type, without any door, window, toilet, bathroom, water supplies,electric wire, bulb or florescent light. (House size. 10feet\*16feet)

2. Whereas labour and shipping would make-up a sizable portion of the total price;

3. This construction is happening through nearly free labour and at-cost government shipping