

UNITED SIKHS ORG.

HAIYAN RELIEF CROSSING LA-IS

FOR ONE HOUSE BUDGET								
S.NO	NAME OF ITEM	SIZE	QUANTITY	PRIZE	SUB TOTAL	TOTAL	\$	IN US\$
1	WOOD	2*5*10	4	233	932		44.05	21.16
2		2*5*16	5	373	1865		44.05	42.34
3		2*5*8	6	186	1116		44.05	25.33
4		2*2*20	15	181	2715		44.05	61.63
5	G.I.S. SHEETS	3*6*.4	18	213	3834		44.05	87.04
6	IREAN ROAD FOR BEAM		54	118	6372		44.05	144.65
7	CEMENT		17	222	3774		44.05	85.68
8	HALLO BLOCKS	4*8*12	250	12	3000		44.05	68.10
9	RIDGE ROLL		15	180	2700		44.05	61.29
10	PLYWOOD FOR BEAMS		6	650	3900		44.05	88.54
11	SAND/GRAVEL	Estimated + -			1500		44.05	34.05
12	NAILS	Estimated + -			400		44.05	9.08
13	LABOUR	1. CARP ENTER & 2 LABOUR		3 DAYS	2000		44.05	45.40
14	BAMBOO/NIPAHUT /PLYWOOD		12	650	7800		44.05	177.07
15	MISCELLANEOUS				2500		44.05	56.75
TOTAL IN PESOS					44408	44408	44.05	1008.13 US\$

NOTE:- 1. This house is studio type, without any door, window, toilet, bathroom, water supplies,electric wire, bulb or florescent light. (House size. 10feet*16feet)

2. Whereas labour and shipping would make-up a sizable portion of the total price;

3. This construction is happening through nearly free labour and at-cost government shipping